

Name of work: Construction of Stone Footpath and Recreation Infrastructural Facilities**Location: Bermo, Botanical Garden, Tingtibi****BOQ**

Sl.No.	Description	Qty.	Unit	Rate(Nu.)	Rate in words	Amount(Nu.)
1	Clearing jungle including uprooting of vegetation & trees of girth < 300mm and disposal within 50m lead.	1400	Sq.m			
2	Earth work in surface excavation, depth <300mm, width >1.5m, area >10 Sq.m in plan, incl. disposal of excavated earth within 50m lead & 1.5m lift and disposed soil to be neatly dressed. Ordinary soil	1050	Sq.m			
3	Excavation in foundation trenches or drains, not exceeding 1.5m in width or area 10 sq.m on plan incl. dressing & ramming, disp. of surplus soil within 50m lead & 1.5m lift: Ordinary soil	252	Cu.m			
4	Proving & laying dry earth bedding, including consolidating each deposited layer by watering, ramming & dressing.	168	Cu.m			

5	Providing & laying hammer dressed dry dolep paving including preparation of bed.40mm	840	Sq.m			
6	Providing & Constructing R.C.C Garden Bench as per design complete including earth work, Jungle clearing and painting	4	each			
	Total amount Nu.					

In words(.....)

Contractors seal & Sign