

Name of Work: Construction of Retaining wall at Digala Beat Office**Gewog : Bardo****BoQ**

SI #	Item Description	Qty.	Unit	Rate	Rate in Words	Amount
1	Earth work in excavation overareas, depth >300mm, width >1.5m, area >10 Sq.m in plan, incl. disposal of excavated earth within 50m lead & 1.5m lift and disposed soil to be neatly dressed. Ordinary soil	189	cum			
2	Excavation in foundation trenches or drains, not exceeding 1.5m in width or area 10 sq.m on plan incl. dressing & ramming, disp. of surplus soil within 50m lead & 1.5m lift: Ordinary soil	29.90	Cu.m			
3	Providing and laying hand packed stone soling or filling with stones .	11.21	Cu.m			
4	Providing and laying in position plain cement concrete excluding the cost of centering and shuttering - All work upto plinth level. 1:3:6 (1 cement : 3 sand : 6 graded crushed rock 40 mm nominal size)	7.47	cu.m			
5	Providing and laying in position plain cement concrete excluding the cost of centering and shuttering - All work upto plinth level. 1:2:4 (1 cement : 2 sand : 4 graded crushed rock 20 mm nominal size)	1.2	cu.m			
6	Providing & laying Random Rubble Masonry with hard stone in found'n & plinth: In cement mortar 1:5	204.25	Cu.m			

7	Filling trenches, sides of foundation, wall, etc including filter material(600m wide)with 200mm stones wherever applicable including filling with selected suitable excavated material in layers not exceeding 200m in depth(compact), consolidating each l	40	cu.m			
---	---	----	------	--	--	--

Total Amount in Nu.....

Rate in words(.....)

Contractors sign & Seal