

**Bill of Quantities for the construction of stone wall at Sakteng WildLife Sanctuary,
Phongmey**

Sl No.	Description	Qty	Units	Rate in Word	Rate in Figure	Amount
1	Excavation in foundation trenches or drains not exceeding 1.5m in width or area 10 sq.m on plan, including dressing & ramming, disposal of surplus soil within 50m lead & 1.5m lift :Hard soil.	124.95	Cu.m			
2	Filling of trenches, sides of foundations etc. in layers <200mm using selected excavated earth, ramming etc, within lead 50m & lift 1.5m	102	Cu.m			
3	Providing & laying Random Rubble Masonry with hard stone in foundation & plinth :In cement mortar 1:4	563.55	Cu.m			
4	Providing and laying in position plain cement concrete excluding the cost of centering and shuttering - All work upto plinth level: 1:3:6 (1 cement:3 sand:6 graded crushed rock 20mm nominal size)	61.2	Cu.m			
Grand Total						